

ENGINEER SEAL

PARTIAL RENOVATION OF LOWER FLOOR
GUNTERSVILLE MUNICIPAL BUILDING
FOR
THE CITY OF GUNTERSVILLE, ALABAMA

DRAWING INDEX		BUILDING CRITERIA		ABBREVIATIONS	
<div>ARCHITECTURAL DRAWINGS:</div> <div>A-GM-01 COVER SHEET</div> <div>A-GM-02 EXISTING WALLS AFTER DEMOLITION BY OWNER</div> <div>A-GM-03 ENLARGED NEW FLOOR PLAN IN WORK AREA- LOWER FLOOR</div> <div>A-GM-04 DIMENSIONED FLOOR PLAN OF WORK AREA</div> <div>A-GM-05 FIRE WALL DELINEATION</div> <div>A-GM-06 TYPICAL DETAILS AT RAISED FLOOR AND PASS WINDOW AT RECORDS ROOM (R012)</div> <div>A-GM-07 DETAILS AT BREAK ROOM, LOCKER ROOM AND BATHROOMS</div> <div>A-GM-08 DOOR SCHEDULE</div> <div>A-GM-09 FINISH SCHEDULE</div> <div>A-GM-10 TYPICAL WALL SECTIONS & TYPICAL HANDICAPPED BATHROOM DETAILS</div> <div>A-GM-11 GENERAL SPECIFICATIONS & NOTES</div> <div>LIFE SAFETY DRAWINGS:</div> <div>L-GM-01 LIFE SAFETY - FIRE ALARM SYSTEM</div> <div>PLUMBING DRAWINGS:</div> <div>P-GM-01 PLUMBING PLAN</div> <div>ELECTRICAL DRAWINGS:</div> <div>E-GM-01 ELECTRICAL - POWER PLAN</div> <div>E-GM-02 ELECTRICAL - LIGHTING PLAN</div> <div>E-GM-03 ELECTRICAL - SPECIFICATIONS</div> <div>E-GM-04 ELECTRICAL - SPECIFICATIONS</div>		<div>APPLICABLE CODES AND STANDARDS:</div> <div>NOTE: WHERE CONFLICTS EXIST BETWEEN CODES AND STANDARDS LISTED BELOW, THE MORE STRINGENT SHALL GOVERN.</div> <div>2006 IBC MECHANICAL CODE</div> <div>2006 IBC PLUMBING CODE</div> <div>2006 INTERNATIONAL BUILDING CODE (IBC)</div> <div>2005 NATIONAL ELECTRICAL CODE.</div> <div>2010 AMERICANS WITH DISABILITIES ACT (ADA)</div> <div>2007 ASHRAE HANDBOOK OF FUNDAMENTALS.</div>		<div>NOT IN CONTRACT</div> <div>GYP-SUM GYPSUM</div> <div>BD- BOARD</div> <div>BLK- BLOCK</div> <div>AC AIR CONDITIONING</div> <div>ADA AMERICAN WITH DISABILITIES ACT, 2010</div> <div>AL ALUMINUM</div> <div>BD BOARD</div> <div>BLDG BUILDING</div> <div>BOTT BOTTOM</div> <div>BRK BRICK</div> <div>CL CLEAR</div> <div>CONC CONCRETE</div> <div>CONT CONTINUOUS</div> <div>DR DOOR</div> <div>EXIST EXISTING</div> <div>EXP EXPANSION</div> <div>FT FOOT</div> <div>FTG FOOTING(S)</div> <div>GALV GALVANIZED</div> <div>GRD GRADE</div> <div>GYP GYPSUM</div> <div>HC HANDICAPPED</div> <div>HM HOLLOW METAL</div> <div>HORZ HORIZONTAL</div> <div>HVAC HEATING, VENTILATING & AIR CONDITIONING</div> <div>IBC INTERNATIONAL BUILDING CODE, 2006</div> <div>JOINT</div> <div>JT LAVATORY</div> <div>LAV LEFT HAND</div> <div>LH LEFT HAND REVERSE</div> <div>LHR LEFT HAND REVERSE</div> <div>LHRA LEFT HAND REVERSE ACTIVE</div> <div>MA MASONITE</div> <div>FLR FLOOR</div> <div>MAX MAXIMUM</div> <div>MFG MANUFACTURER</div> <div>MIN MINIMUM</div> <div>MINU MINUTE</div> <div>NEC NATIONAL ELECTRIC CODE, LATEST EDITION</div> <div>O.D. OUTSIDE DIAMETER</div> <div>OS OPPOSITE SWING</div> <div>OSHA OCCUPATIONAL SAFETY & HEALTH ACT</div> <div>REQ'D REQUIRED</div> <div>RH RIGHT HAND</div> <div>RHR RIGHT HAND REVERSE</div> <div>RHRA RIGHT HAND REVERSE ACTIVE</div> <div>SF SQUARE FOOT</div> <div>SIM SIMILAR</div> <div>SQ SQUARE</div> <div>SWD SOLID WOOD DOOR</div> <div>SYS SYSTEM</div> <div>THK THICK</div> <div>TYP TYPICAL</div> <div>UN UNLESS NOTED</div> <div>UR URINAL</div> <div>VERT VERTICAL</div> <div>WC WATER CLOSET</div> <div>WD WOOD</div> <div>AWI ARCHITECTURAL WOODWORK INST.</div>	
<div>NOTES:</div> <div>1. ALL HVAC WORK: EQUIPMENT, DUCTS, DIFFUSERS, RETURNS, ETC. SHALL BE FURNISHED AND INSTALLED BY OWNER.</div> <div>2. ALL EXTERIOR WINDOW AND DOOR REPLACEMENT ON EXTERIOR WALLS SHALL BE FURNISHED AND INSTALLED BY OWNER.</div> <div>3. THE EXTERIOR DOOR TO THE WAITING ROOM, ROOM R111, SHALL BE FURNISHED AND INSTALLED BY OWNER.</div> <div>4. CONTRACTOR SHALL VERIFY ALL DIMENSIONS & ELEVATIONS IN FIELD BEFORE ORDERING MATERIALS AND EQUIPMENT.</div> <div>5. CONTRACTOR SHALL REPAIR OR REPLACE ALL DAMAGED SUBSTRATES AS REQUIRED: WALLS, FLOORS, ETC., PRIOR TO APPLICATION OF FINISHES.</div> <div>6. CONTRACTOR SHALL PROPERLY PREPARE, REPAIR OR LEVEL ALL SUBSTRATES: WALLS, FLOORS, ETC., PRIOR TO APPLICATION OF FINISHES.</div> <div>7. SEE DRAWING A-GM-08 FOR DOOR NUMBERS AND A-GM-09 FOR ROOM NUMBERS.</div> <div>8. LEVEL ALL FLOORS PRIOR TO INSTALLING FLOORING.</div> <div>9. BLINDS FOR EXTERIOR WINDOWS WILL BE FURNISHED & INSTALLED BY OWNER.</div> <div>10. SEE DRAWING E-GM-(?) FOR CEILING GRID LAYOUT.</div> <div>11. CONTRACTOR SHALL VERIFY OPENING SIZES AND LOCATIONS PRIOR TO ORDERING NEW INTERIOR DOORS OR INTERIOR WINDOWS.</div> <div>12. CONTRACTORS SHALL VERIFY EXISTING JOB CONDITIONS BEFORE BIDDING WORK AND SHALL NOTIFY ARCHITECT OF ANY CONFLICTS OR PROBLEMS WITH DOING WORK REQUIRED BY PLANS & SPECIFICATIONS.</div> <div>13. CONTRACTOR SHALL PROVIDE TEMPORARY PARTITION(S) OR BARRIERS WHERE REQUIRED TO PREVENT THE SPREAD OF DUST. PATHS OF EGRESS SHALL NOT BE BLOCKED.</div> <div>13. CONTRACTOR SHALL PROVIDE SIGNAGE AT ALL DOORS IDENTIFYING ROOMS. SIGNAGE SHALL MATCH SIGNAGE ON UPPER LEVEL OF BUILDING, UNLESS NOTED DIFFERENTLY.</div>		<div>REVISIONS</div> <div>DATE 08/28/17</div> <div>BY E.D. SMITH</div> <div>FOR E.D. SMITH</div> <div>DESIGN</div>		<div>5450</div> <div>FOR BIDS</div> <div>DESIGNED BY E.D. SMITH</div> <div>DATE 08/28/17</div>	
<div>COVER SHEET</div> <div>1/8"=1'-0"</div> <div>A-GM-01</div>		<div>REVISIONS</div> <div>DATE 08/28/17</div> <div>BY E.D. SMITH</div> <div>FOR E.D. SMITH</div> <div>DESIGN</div>		<div>5450</div> <div>FOR BIDS</div> <div>DESIGNED BY E.D. SMITH</div> <div>DATE 08/28/17</div>	